

Toza India Pvt Enterprise

227 – Neelkanth Arcade, Near CNI Church, Oppo St Joseph Academy,
43 – Rajpur Road, Dehradun, Uttarakhand, India – 248001

9758828989, 9058002121

Web - www.TozaIndia.com

Email – info@TozaIndia.com

Name : -

Occupation : - Govt Job / Private Job / Self Employee / Business Owner / Others

Address :-

Phone : - Office Res (M)

Capacity of Tank (As per clients) : - Uses X 01 X 02 X 03 X 04 X 05 X 06 X 07 X 08 X 09 X 10

No	Uses	Charge in Dehradun / Unit	Other Cities / Unit	Remarks
1	20	39900/-	49900/-	Including excavation and installation
2	30	59900/-	79900/-	Including excavation and installation
3	50	99900/-	129900/-	Including excavation and installation
4	70	139900/-	179900/-	Including excavation and installation
5	100	239900/-	299900/-	Including excavation and installation

For Big size projects septic tanks in multiple may be used like for 500 uses, 05 units of 100 uses shall be installed

100% Advance Payment to be paid at the time of order: - Rs

Difference That Makes the Difference: - Many domestic and commercial septic tank designs are being used nowadays in our country where sewer lines do not exist; like three chamber brick made or RCC septic tank in deferent trade names. When we talk about Readymade, Precasted or RCC pipe septic tank; the most common shape comes in people's mind that is circular one. The circular shape Septic Tank was developed long back in 1970s and widely being used by many people. The circular shape septic system was tested by CBRI Roorkee in 1995 and they found some setbacks in the design and recommended some possible improvements to enhance its efficiency. As everyone knows that we live in technological age and technology is changing very fast so the septic tank design created on or before 1970 will not help in the present context hence we have improved the design as per the recommendation of CBRI and innovated a Sewer Disposal system called **EmptiNil BioFurnaX** Septic Tank that is based on new technologies, have valuable features like SAM (Self Developed Strong Anaerobic Microorganism), H shaped inter connector, ACPC (Auxiliary Chamber cum Proficient Clarifier), Eco-T outlet and a UASC (Up flow Anaerobic Sludge Coverlet system).

Our Scope of Work: - Excavation, Installation and supply of Pre-casted **EmptiNil BioFurnaX** called Readymade Septic Tank's chambers with 4" diameter, 6" long inlet / outlet connection and fabrication of round shape RCC covers are in our scope of work. Any other work like Plumbing, Flooring, extra soil removal, Soak Pit, sewer pipe lines etc, main hole chambers, local transportation of **EmptiNil BioFurnaX**, a Readymade Septic Tank System, required material for construction like cement, sand, steel etc, other civil and sanitary work not included. Water filling inside tank for hydro testing shall be arranged by customer. Rates have been quoted for normal soil. For hard rock or watery conditions rates shall be quoted extra.

Other relevant Details: - The RCC round shape chambers of **EmptiNil BioFurnaX** called Readymade Septic Tank of required capacity shall be supplied and installed in parts. Complete fitting and other connections like inlet / outlet and center connections shall be done at site after exact measurement of levels. Sealing of tank bottom and top covers shall also be prepared at site during installation work. Users / customers need to fill these Readymade Septic tanks with water completely before use and always maintain water at full level as the operation / working of this system is water based. Before signing this agreement; it has been made clear to customer / client that AutoClean warrantee is valid if other houses hold waste water like bathroom etc passed through filtration tank and outlet connection of this tank is connected to running drain. If drain is absent then multi soak well system shall be constructed and used alternatively and separate drainage system shall be developed for other household like bathroom/kitchen water. The inlet / center / outlet path of septic tank should be kept clear always by customer / user to achieve its full effectiveness.